

atment & Recovery Services

July 27, 1994

To:

Mr. Steve Broslavick

Hazardous Waste Section

Kansas Department of Health and Environment

Forbes Field, Building 740 Topeka, Kansas 66620-0002

From:

Ron Robertson

Re:

Hydrocarbon Recyclers, Inc. of Wichita EPA ID Number KSD007246846

CLUEIVEI Bureau of

JUL 2 8 1994

WASTE MANAGEMENT

PRICE

Part B Permit Application

Corrections to Building I Containment

Enclosed you will find the revised text and drawings for the Building I revisions to the Part B Permit Application. In Section D, the following pages were revised: pp. 5, 8, 13, 34, 35, 36. Please note that although pages 34, 35, and 36 have been changed, pages 34A and 35A have not been changed.

- The only page changed in Section J is the second page of Appendix J-1 (page 66 in the text).
- Drawings numbers 50-17-10-001, 50-01-10-002, 50-30-3-001, and the "I-Building Safety" drawing have been changed, and will need to be replaced in Section Y, Referenced Drawings. Reduced copies of these drawings are also included for insertion into the text.
- The reorganization of container management units (CMUs) in Building I from four units to three units has necessitated the recalculation of the containment volumes, although it has not changed the total waste storage volume for the building. The new calculations for CMUs I100, I200, and I300 are provided for insertion into Appendix D-B, Attachment 6.

Please call me if you have any further questions.

Sincerely,

Ronald K. Robertson Facility Compliance Officer

cc:

S. Keiter

L. Hetherington-Ward

D. Hensch

RECEIVED

AUG 4 1994

PRIVIT SECTION

Our Mission:

RCRA Records Center




Figure D.2. Material Containment Areas

Page 5

July 21, 1994 Revision No. 2

Table D.2

CMU Containment Summary

Container Management Unit (CMU)	Maximum Number of Drums Stored (55 gallon drum equivalents)		Gallons - Containment Capacity Required for Containers (10 %	Gallons - Containment Provided		
	Drums	Gallons	Container Capacity)			
D100/D200	784	43,120	4,312	13,480		
D300	64	3,520	352	3,606		
P100/P200	180	9,900	990	32,583		
C100	16	880	88	244		
C200	16	880	88	192		
C300	240	13,200	1,320	3,842		
C400	184	10,120	1,012	3,195		
C500	192	10,560	1,056	3,233		
C600	192	10,560	1,056	3,233		
C700	962	52,910	5,291	16,690		
L100	272	14,960	1,496	1,835		
B100	120	6,600	660	2,262		
B200	384	21,120	2,112	5,592		
B300	360	19,800	1,980	5,630		
B400	136	7,480	748	2,582		
I100	416	22,880	2,288	4,503		
1200	64	3,520	352	635		
1300	440	24,200	2,420	6,088		

treated in containers. Rooms and diking in this building will provide containment for three (3) separate CMUs.

D-1g Building J:

Building J is designated for container storage, treatment, and management. Waste managed in this area may be processed or treated in containers. Rooms and diking in this building will provide containment for seven (7) separate CMUs.

D-2h Building I:

Referenced Drawings

Drawing 50-17-10-001 Building I

Building I is an existing Interim Status waste management area that has undergone renovation. This section has been written to recognize the configuration and usage of Building I as it will be operated now that the renovations are completed.

Building I has been designed to manage containerized wastes in three (3) contained areas (CMUs). Containerized wastes managed in this building include ignitable, non-ignitable, reactive, non-reactive and other hazardous and non-hazardous wastes. These materials are destined primarily for off-site management, but may also be destined for on-site management, recycling as waste fuel, waste water management, or solvent recovery. Processing of containerized wastes in Building I may involve treatment in containers, repackaging or management in any of the several on-site processing units.

D-2h(1) <u>Secondary Containment:</u>

Building I is designed with three (3) CMUs (I100 through I300) which are diked or walled to provide secondary containment. The layout of Building I is shown on Figure D.8 (Drawing 50-17-10-001), presented in Appendix D-A. The CMUs are designed to meet the storage requirements for RCRA regulated wastes, to promote sound container management practices, and to minimize the potential for a release of hazardous waste into the environment. The CMUs are constructed of concrete floors and diking, and concrete block walls. Seams in the floor are sealed using water stops.


40 CFR 264.175(b)(3) requires that the secondary containment system contain the volume of the largest container, or ten (10)


D-2h(2) Building Design:


Building I has been subdivided into three (3) CMUs. The building has an overall size of approximately one-hundred-six (106) feet long by forty-eight (48) feet wide. Waste containers managed in Building I are palletized or equipped with skids during storage, or are otherwise managed to protect the outside walls of the containers from contact with accumulated liquids. Some management of containers may occur directly on the concrete floor (e.g., during processing). Concrete curbs or walls around the unit or portable containment units provide secondary containment. Adequate secondary containment volume is provided for this building, as described in D-2h(1).


Hydrocarbon Recyclers, Inc. of Wichita RCRA Permit Application Section J Closure Plan Appendix J-A - Tables

<u>HWMU</u>	UNIT	WASTES STORED/FUNCTION
С	CMU B400	Hazardous waste - Container Management
С	CMU D100	Hazardous waste - Container Management
С	CMU D200	Hazardous waste - Container Management
С	CMU D300	Hazardous waste - Container Management
С	CMU I100	Hazardous waste - Container Management
С	CMU 1200	Hazardous waste - Container Management
С	CMU 1300	Hazardous waste - Container Management
С	CMU J100	Hazardous waste - Container Management
С	CMU J200	Hazardous waste - Container Management
С	CMU J300	Hazardous waste - Container Management
С	CMU J400	Hazardous waste - Container Management
С	CMU J500	Hazardous waste - Container Management
С	CMU J600	Hazardous waste - Container Management
С	CMU J700	Hazardous waste - Container Management
С	CMU L100	Hazardous waste - Container Management
С	CMU P100	Hazardous waste - Container Management
С	CMU P200	Hazardous waste - Container Management
T	V-1	Hazardous Waste Liquid
T	V-2	Hazardous Waste Liquid
T	V-3	Hazardous Waste Liquid
T	V-4	Hazardous Waste Liquid









CONTAINMENT QUANTITIES

I-100 = 4,503 GALLONS

I-200 = 635 GALLONS

I-300 = 6,088 GALLONS

FIRE SUPPRESSION SYSTEMS

I-100 = DELUGE SYSTEM ACTIVATED BY EXPLOSION PROOF HEAT DETECTERS

I-200 = DRY CHEMICAL SYSTEMS ACTIVATED BY HEAT DETECTERS

I-300 = DELUGE SYSTEM ACTIVATED BY HEAT DETECTORS AND UV - FLAME DETECTORS

USPCI - HRI WICHITA SECONDARY CONTAINMENT CALCULATION

BUILDING - I

Volume Provided - Calculated to exclude ramps and curbs. External ramps and curbs are 9 inches high.

AREA I - 100

Outer boundaries Volume I - 100	[0.33'x(29.75'x 58.25')]+ [0.33'x(17.58'x 15')]	=		659	ft³
Entrance ramp west end	[(24'x 2.2'x 0.33)] + [24'x(0.5x 1.8'x 0.33')]	=	_	24	ft³
Entrance pedestal south door	(4'x 4'x 0.33')	=	_	5	ft³
Entrance pedestal south door	(4'x 4'x 0.33')	=	_	5	ft³
Entrance pedestal north door	(6'x 6'+ 4.5'x 8')x 0.33	<u>=</u>		23	ft³
Total Volume I - 100		=		602	ft^3
or		=	4.	503	gals

^{*} Maximum number of drums in Area I - 100 is 416 drums. This would require containment for 10% of (416×55) gallons or 2,288 gallons of containment needed.

Area I - 200

Outer boundaries
Volume Area I - 200 (19.33'x 16'x 0.33') = 102 ft³

Entrance pedestal north side $[(4'x \ 4') + (6'x \ 6')]x \ 0.33' = -17 ft³$ Total Volume Area I - 200 = 85 ft³

or = 635 gals

^{*} Maximum number of drums in Area I - 200 is 64 drums. This would require containment for 10% of (64 x 55) gallons or 352 gallons of containment needed.

Area I - 300

Outer boundaries
Volume Area I - 300

south	(12'x 2.2'x 0.33')+ (12'x 0.5 x 1.8'x 0.33')	=	- 12	ft³
south		=	- 12	ft^3
		=	- 12	ft³
	(12'x 0.5 x 1.8'x 0.33')	=	- 12	ft ³
		=	- 12	ft^3
South		=	- 12	ft^3
-				c . 3
Entrance ramp				
	(4·X 4·X 0.33·)		- 5	I L
Entrance pedestal central door	(4'x 4'x 0.33')	=	- 5	ft^3
Entrance nedestal				
south door	(4'x 4'x 0.33')	=	- 5	ft^3
Entrance pedestal				
north door	(4'x 4'x 0.33')	=	- 5	ft³
Entrance pedestal				
	[30'x 47'x 0.33]	=	853	It
	[27'x 16.5'x 0.33]+		0.53	3
	[17'x 43'x 0.33']+			
Volume Area I - 300				

^{*} Maximum number of drums in Area I - 300 is 440 drums. This would require containment for 10% of (440 x 55) gallons or 2,420 gallons of containment needed.

I - BUILDING SUMMARY

Total Volume Provided

Area I - 100 = 4,503 gals

Area I - 200 = 635 gals

Area I - 300 = 6.088 gals

Total 11,226 gals


Total Volume Provided - Storage Capacity x 10% + Gallons of Extra Capacity =


Area I - 100 4,503 gals - $(22,880 \text{ gals } \times 10\%)$ = 2,215 gals

Area I - 200 635 gals - (3,520 gals x 10%) = 283 gals

Area I - 300 6,088 gals - $(24,200 \text{ gals } \times 10\%)$ = 3,668 gals

Total gallons of extra capacity 6,166 gals





CONTAINMENT QUANTITIES

1-100 = 4,503 GALLONS

1-200 = 635 GALLONS

1-300 = 6,088 GALLONS

FIRE SUPPRESSION SYSTEMS

1-100 = DELUGE SYSTEM ACTIVATED BY EXPLOSION PROOF HEAT DETECTERS

-200 = DRY CHEMICAL SYSTEMS ACTIVATED BY HEAT DETECTERS

1-300 = DELUGE SYSTEM ACTIVATED BY HEAT DETECTORS AND UV - FLAME DETECTORS

a plan for SAFETY EQUIPMENT to the Hydrocarbon Recyclers, Inc. a Division of USPCI located at 2549 N. New York Ave. Wichita, Kansas 67219

SHEET

